



## STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

SEAC-2016/C.R.424/TC-1 Environment department,  
Room No. 217, 2nd floor,  
Mantralaya, Annexe,  
Mumbai- 400 032.  
Date: July 3, 2017

To,  
**Amendment in Environment Clearance "PROPOSED COMMERCIAL DEVELOPMENT on plot bearing at C.S. No. 612 & 613, Lower Parel Division, Elphinstone Mill, Senapati Bapat Marg, Mumbai - 400013. State- Maharashtra.**

at Lower Parel Division 612 and 613, Elphinstone Mill, Senapati Bapat Marg, Mumbai 400013

**Subject:** Environment Clearance for Amendment in Environment Clearance

Sir,

This has reference to your communication on the above mentioned subject. The proposal was considered as per the EIA Notification - 2006, by the State Level Expert Appraisal Committee-II, Maharashtra in its th meeting and recommend the project for prior environmental clearance to SEIAA. Information submitted by you has been considered by State Level Environment Impact Assessment Authority in its SEIAA Meeting No. 110th meetings.

2. It is noted that the proposal is considered by SEAC-II under screening category 8 (b) B1 as per EIA Notification 2006.

**Brief Information of the project submitted by you is as below :-**

1.Name of Project	Amendment in Environment Clearance "PROPOSED COMMERCIAL DEVELOPMENT on plot bearing at C.S. No. 612 & 613, Lower Parel Division, Elphinstone Mill, Senapati Bapat Marg, Mumbai - 400013. State- Maharashtra.
2.Type of institution	Private
3.Name of Project Proponent	Indiabulls Real Estate Co. Pvt. Ltd. - Mr. Purav Acharya
4.Name of Consultant	Mahabal Enviro Engineers Pvt. Ltd. Thane, Maharashtra.
5.Type of project	Commercial Project
6.New project/expansion in existing project/modernization/diversification in existing project	Modernization in Existing Project - Amendment in EC
7.If expansion/diversification, whether environmental clearance has been obtained for existing project	Environment Clearance File Number SEAC - 2010/CR-180/TC-2 received on 23.01.2012 from Government of Maharashtra
8.Location of the project	Lower Parel Division 612 and 613, Elphinstone Mill, Senapati Bapat Marg, Mumbai 400013
9.Taluka	Mumbai
10.Village	Lower Parel
11.Area of the project	Municipal Corporation of Greater Mumbai (MCGM)
12.IOD/IOA/Concession/Plan Approval Number	IOD IOD/IOA/Concession/Plan Approval Number: IOD File No. EB/1642/GN/A Dated 26.07.2006 Approved Built-up Area: 126168
13.Note on the initiated work (If applicable)	Wing A, B & C work completed as per earlier EC dated 23rd January 2012 and which are already commissioned as per part Consent to Operate received (ref. no. BO/CAC-Cell/CR(part)/CAC/MU-6488-15/CAC-10801 dated 05.12.2016). As per earlier EC issued dated 23rd January 2012, Construction work for Wing D (as per residential) is completed upto podium levels.
14.LOI / NOC / IOD from MHADA/ Other approvals (If applicable)	Other approval - Public Parking Lot (PPL) LOI received
15.Total Plot Area (sq. m.)	34,383 sq.mt.
16.Deductions	2,841 sq.mt.
17.Net Plot area	31,542 sq.mt.
18.Proposed Built-up Area (FSI & Non-FSI)	FSI area (sq. m.): 1,26,168 Non FSI area (sq. m.): 2,33,931 m2 Total BUA area (sq. m.): Office Buildings (Wing A,B & C) - 1,68,909 and wing D 99,995 m2 and MCGM Parking 91,195
19.Total ground coverage (m2)	19,694

SEIAA Meeting No: SEIAA Meeting No. 110 Meeting Date: May 3,  
2017 ( SEIAA-STATEMENT-000000072 )  
SEIAA-MINUTES-0000000114  
SEIAA-EC-0000000134

Page 1 of 12

Shri Satish.M.Gavai (Member  
Secretary SEIAA)

20.Ground-coverage Percentage (%) (Note: Percentage of plot not open to sky)	57
21.Estimated cost of the project	5690000000



# Government of Maharashtra

Shri Satish.M.Gavai (Member  
Secretary SEIAA)

## 22. Production Details

Serial Number	Product	Existing (MT/M)	Proposed (MT/M)	Total (MT/M)
1	Not applicable	Not applicable	Not applicable	Not applicable

## 23. Total Water Requirement

<b>Dry season:</b>	Source of water	MCGM
	Fresh water (CMD):	379
	Recycled water - Flushing (CMD):	338
	Recycled water - Gardening (CMD):	264
	Swimming pool make up (Cum):	Not Applicable
	Total Water Requirement (CMD) :	867
	Fire fighting - Underground water tank(CMD):	1400
	Fire fighting - Overhead water tank(CMD):	Not Applicable
	Excess treated water	0
<b>Wet season:</b>	Source of water	MCGM
	Fresh water (CMD):	379
	Recycled water - Flushing (CMD):	338
	Recycled water - Gardening (CMD):	250
	Swimming pool make up (Cum):	Not Applicable
	Total Water Requirement (CMD) :	867
	Fire fighting - Underground water tank(CMD):	1400
	Fire fighting - Overhead water tank(CMD):	Not Applicable
	Excess treated water	0
<b>Details of Swimming pool (If any)</b>	Not Applicable	

Government of Maharashtra




## 24.Details of Total water consumed

Particulars	Consumption (CMD)			Loss (CMD)			Effluent (CMD)		
	Existing	Proposed	Total	Existing	Proposed	Total	Existing	Proposed	Total
Domestic	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable

<b>25.Rain Water Harvesting (RWH)</b>	<b>Level of the Ground water table:</b>	4.0 to 6.50 m
	<b>Size and no of RWH tank(s) and Quantity:</b>	RW collection tank of total capacity 100 CMD for Wing D and 400 CMD for Wing A, B, C
	<b>Location of the RWH tank(s):</b>	at Basement Level
	<b>Quantity of recharge pits:</b>	Recharge the ground water sources through 6 multiple ring wells and 7 nos of ring wells
	<b>Size of recharge pits :</b>	1.5 m diameter
	<b>Budgetary allocation (Capital cost) :</b>	Rs.38.90 Lakh
	<b>Budgetary allocation (O &amp; M cost) :</b>	Rs.1.95 Lakh/Years
<b>Details of UGT tanks if any :</b>	Location of UGT tank is at level and capacity of UGT tank is are given below Domestic Tank capacity: A. Wing A, B, C office building : 600 m <sup>3</sup> B. Wing D office building : 300 m <sup>3</sup> C. MCGM Car Parking : 20 m <sup>3</sup> Flushing Tank capacity : A. Wing A, B, C office building : 300 m <sup>3</sup> B. Wing D office building : 120 m <sup>3</sup> C. MCGM Car Parking : 10 m <sup>3</sup> Fire Tank capacity : A. Wing A, B, C office building : 600 m <sup>3</sup> B. Wing D office building : 400 m <sup>3</sup> C. MCGM Car Parking : 400 m <sup>3</sup>	

<b>26.Storm water drainage</b>	<b>Natural water drainage pattern:</b>	As per contour
	<b>Quantity of storm water:</b>	0.69 m <sup>3</sup> /sec
	<b>Size of SWD:</b>	600 mm Diameter


<b>27.Sewage and Waste water</b>	<b>Sewage generation in KLD:</b>	542
	<b>STP technology:</b>	MBBR
	<b>Capacity of STP (CMD):</b>	2 Nos. of STP and for wing D - 200 KLD and for wing A, B, C - 450 KLD
	<b>Location &amp; area of the STP:</b>	Location of the STP at Basement level and area dor 450 KLD is 405.55 sq.mt. (wing A, B, C) and area for 200 KLD is 372.15 sq.mt. (wing D)
	<b>Budgetary allocation (Capital cost):</b>	78.73 Lakh
	<b>Budgetary allocation (O &amp; M cost):</b>	24.20 Lakh/year



## 28.Solid waste Management

<b>Waste generation in the Pre Construction and Construction phase:</b>	<b>Waste generation:</b>	176 kg/day
	<b>Disposal of the construction waste debris:</b>	Debris generated will be sent to the authorized debris disposal site as per
<b>Waste generation in the operation Phase:</b>	<b>Dry waste:</b>	833 kg/day
	<b>Wet waste:</b>	1,665 kg/day
	<b>Hazardous waste:</b>	Not Applicable
	<b>Biomedical waste (If applicable):</b>	Not Applicable
	<b>STP Sludge (Dry sludge):</b>	6 kg/day
	<b>Others if any:</b>	E-Waste 83 kg/day and inert waste 194 kg/day
<b>Mode of Disposal of waste:</b>	<b>Dry waste:</b>	will send to authorised vendor
	<b>Wet waste:</b>	will convert into compost and use for gardening
	<b>Hazardous waste:</b>	Not Applicable
	<b>Biomedical waste (If applicable):</b>	Not Applicable
	<b>STP Sludge (Dry sludge):</b>	use as manure
	<b>Others if any:</b>	E-Waste: E - Waste from Commercial development (IT Park) will be such as keyboard, CD's, discarded monitors etc. will be handed over to authorized dealers
<b>Area requirement:</b>	<b>Location(s):</b>	On ground
	<b>Area for the storage of waste &amp; other material:</b>	150 sq.mt
	<b>Area for machinery:</b>	75 sq.mt.
<b>Budgetary allocation (Capital cost and O&amp;M cost):</b>	<b>Capital cost:</b>	16 Lakh
	<b>O &amp; M cost:</b>	2.4 Lakh/year

# Government of Maharashtra



## 29.Effluent Charecterestics

Serial Number	Parameters	Unit	Inlet Effluent Charecterestics	Outlet Effluent Charecterestics	Effluent discharge standards (MPCB)
1	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable
Amount of effluent generation (CMD):		Not applicable			
Capacity of the ETP:		Not applicable			
Amount of treated effluent recycled :		Not applicable			
Amount of water send to the CETP:		Not applicable			
Membership of CETP (if require):		Not applicable			
Note on ETP technology to be used		Not applicable			
Disposal of the ETP sludge		Not applicable			



# Government of Maharashtra



### 30. Hazardous Waste Details

Serial Number	Description	Cat	UOM	Existing	Proposed	Total	Method of Disposal
1	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable

### 31. Stacks emission Details

Serial Number	Section & units	Fuel Used with Quantity	Stack No.	Height from ground level (m)	Internal diameter (m)	Temp. of Exhaust Gases
1	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable

### 32. Details of Fuel to be used

Serial Number	Type of Fuel	Existing	Proposed	Total
1	Not applicable	Not applicable	Not applicable	Not applicable

Source of Fuel: Not applicable  
 Mode of Transportation of fuel to site: Not applicable

### 33. Energy

<b>Power requirement:</b>	Source of power supply :	BEST
	During Construction Phase: (Demand Load)	300 kVA
	DG set as Power back-up during construction phase	Not Applicable
	During Operation phase (Connected load):	23.15 MW
	During Operation phase (Demand load):	18.40 MW
	Transformer:	Wing A-2 nos. x 2000 kVA each, Wing B & C-6 nos. x 2500 kVA each, Wing D-3 nos. x 2000 kVA each, MCGM Car parking - 1 no. x 2500 kVA
	DG set as Power back-up during operation phase:	Wing A, B, & C-7 nos. x 2000 kVA each, Wing D-4 nos. x 2000 kVA each, MCGM Car parking - 2 nos. x 1250 kVA each
	Fuel used:	As per requirement
	Details of high tension line passing through the plot if any:	Not Applicable

### 34. Energy saving by non-conventional method:

Use of CFL, T5 Lamps, Timer based external lightings and all cables de-rated

### 36. Detail calculations & % of saving:


Serial Number	Energy Conservation Measures	Saving %
1	Use of CFL, T5 Lamps, Timer based external lightings and all cables de-rated	20%

### 37. Details of pollution control Systems

Source	Existing pollution control system	Proposed to be installed
Not applicable	Not applicable	Not applicable

<b>Budgetary allocation (Capital cost and O&amp;M cost):</b>	Capital cost:	Rs.35 Lakh
	O & M cost:	Rs.0.70 Lakh/year

### 38. Environmental Management plan Budgetary Allocation

<p><b>SEIAA Meeting No: SEIAA Meeting No. 110 Meeting Date: May 3, 2017 ( SEIAA-STATEMENT-000000072 )</b>  <b>SEIAA-MINUTES-0000000114</b>  <b>SEIAA-EC-0000000134</b></p>	<div style="text-align: center;">   <b>Shri Satish.M.Gavai (Member Secretary SEIAA)</b> </div> <p style="text-align: center;">Page 7 of 12</p>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

<b>a) Construction phase (with Break-up):</b>			
Serial Number	Attributes	Parameter	Total Cost per annum (Rs. In Lacs)
1	Water for Dust suppression	pH, Colour, odour, turbidity, Total hardness	1.30
2	Site Sanitation	Disinfection	2.0
3	Disinfection (Pest Control)	Disinfection	3.6
4	Health Check up	Monthly	1.5
5	Personal Protective Equipments	Safety jacket, Safety shoes, Helmate, Belt	1.5
6	Landscape Set up	Soil and Water	10.5
7	Training and Awareness	Weekly	0.8
8	First Aid Facilities	First Aid Box	0.2
9	Environmental Monitoring	Air, Water, Soil and Noise Monitoring	2.4


<b>b) Operation Phase (with Break-up):</b>				
Serial Number	Component	Description	Capital cost Rs. In Lacs	Operational and Maintenance cost (Rs. in Lacs/yr)
1	Sewage Treatment Plant	STP having capacity 650 KLD	78.75	24.20
2	Landscape Development	RG Area	43.46	6.95
3	Solid Waste Management	Composting	16.00	2.40
4	Rain water Harvesting	Channelizing and maintenance of rain water harvesting	38.90	1.95
5	Storm Water Harvesting	Channelizing and maintenance of Storm water drainage line	40.00	2.0
6	Energy Conservation	Solar	35.00	0.70
7	Fire Fighting	As per norms	45	1.5
8	Environment Monitoring	Air, Water, Soil and Noise Monitoring	15.00	2.40

### 39.Storage of chemicals (inflammable/explosive/hazardous/toxic substances)

Description	Status	Location	Storage Capacity in MT	Maximum Quantity of Storage at any point of time in MT	Consumption / Month in MT	Source of Supply	Means of transportation
Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable

### 40.Any Other Information

No Information Available





	<b>CRZ/ RRZ clearance obtain, if any:</b>	Not Applicable
	<b>Distance from Protected Areas / Critically Polluted areas / Eco-sensitive areas/ inter-State boundaries</b>	Not Applicable
	<b>Category as per schedule of EIA Notification sheet</b>	8 (b) B1
	<b>Court cases pending if any</b>	Not Applicable
	<b>Other Relevant Informations</b>	We had received the Environment Clearance file No. SEAC-2010/CR-180/TC-2 dated 23rd January 2012 from govt. of Maharashtra and Wing A, B & C work completed as per earlier EC dated 23rd January 2012 and which are already commissioned as per part Consent to Operate received (ref. no. BO/CAC-Cell/CR(part)/CAC/MU-6488-15/CAC-10801 dated 05.12.2016)As per earlier EC issued dated 23rd January 2012, Construction work for Wing D (as per residential) is completed upto podium levels.
	<b>Have you previously submitted Application online on MOEF Website.</b>	No
	<b>Date of online submission</b>	-


**3. The proposal has been considered by SEIAA in its SEIAA Meeting No. 110th meeting & decided to accord environmental clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implementation of the following terms and conditions:**

**Specific Conditions:**

**General Conditions:**


<b>I</b>	E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
<b>II</b>	The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
<b>III</b>	This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.
<b>IV</b>	PP has to abide by the conditions stipulated by SEAC & SEIAA.
<b>V</b>	The height, Construction built up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body & it should ensure the same along with survey number before approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.
<b>VI</b>	If applicable "Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
<b>VII</b>	All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.
<b>VIII</b>	Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
<b>IX</b>	The solid waste generated should be properly collected and segregated. dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
<b>X</b>	Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
<b>XI</b>	Arrangement shall be made that waste water and storm water do not get mixed.
<b>XII</b>	All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
<b>XIII</b>	Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
<b>XIV</b>	Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.

**SEIAA Meeting No: SEIAA Meeting No. 110 Meeting Date: May 3, 2017 ( SEIAA-STATEMENT-000000072 )  
SEIAA-MINUTES-0000000114  
SEIAA-EC-0000000134**




**Shri Satish.M.Gavai (Member Secretary SEIAA)**

XV	Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
XVI	Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate watercourses and the dumpsites for such material must be secured so that they should not leach into the ground water.
XVII	Any hazardous waste generated during construction phase should be disposed off as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
XVIII	The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
XIX	The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from concern authority shall be taken.
XX	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
XXI	Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
XXII	Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27th August, 2003. (The above condition is applicable only if the project site is located within the 100Km of Thermal Power Stations).
XXIII	Ready mixed concrete must be used in building construction.
XXIV	Storm water control and its re-use as per CGWB and BIS standards for various applications.
XXV	Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
XXVI	The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
XXVII	The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Discharge of this unused treated effluent, if any should be discharge in the sewer line. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Discharge of this unused treated effluent, if any should be discharge in the sewer line. Treatment of 100% gray water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP.
XXVIII	Permission to draw ground water and construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
XXIX	Separation of gray and black water should be done by the use of dual plumbing line for separation of gray and black water.
XXX	Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
XXXI	Use of glass may be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.
XXXII	Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.
XXXIII	Energy conservation measures like installation of CFLs /TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible like installing solar street lights, common solar water heaters system. Project proponent should install, after checking feasibility, solar plus hybrid non-conventional energy source as source of energy.
XXXIV	Diesel power generating sets proposed as source of backup power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
XXXV	Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
XXXVI	Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
XXXVII	Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspiration for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.
XXXVIII	The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.
XXXIX	Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.
XL	Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.



<b>XLI</b>	Six monthly monitoring reports should be submitted to the Regional office MoEF, Bhopal with copy to this department and MPCB.
<b>XLII</b>	Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.
<b>XLIII</b>	Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.
<b>XLIV</b>	Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.
<b>XLV</b>	A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB.
<b>XLVI</b>	In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Department.
<b>XLVII</b>	A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
<b>XLVIII</b>	Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB & this department.
<b>XLIX</b>	The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at <a href="http://ec.maharashtra.gov.in">http://ec.maharashtra.gov.in</a> .
<b>L</b>	Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
<b>LI</b>	A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
<b>LII</b>	The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO <sub>2</sub> , NO <sub>x</sub> (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
<b>LIII</b>	The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
<b>LIV</b>	The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.

# Government of Maharashtra



4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environmental Clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.


6. The Environment department reserves the right to add any stringent condition or to revoke the clearance if conditions stipulated are not implemented to the satisfaction of the department or for that matter, for any other administrative reason.

7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, and amendments by MoEF&CC Notification dated 29th April, 2015.

8. In case of any deviation or alteration in the project proposed from those submitted to this department for clearance, a fresh reference should be made to the department to assess the adequacy of the condition(s) imposed and to incorporate additional environmental protection measures required, if any.

9. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

10. Any appeal against this environmental clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-, Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.



Shri Satish.M.Gavai (Member Secretary SEIAA)

**Copy to:**

1. SHRI ANAND. B. KULKARNI, CHAIRMAN-SEIAA
2. SHRI UMAKANT DANGAT, CHAIRMAN-SEAC-I
3. SHRI JOHNY JOSEPH, CHAIRMAN-SEAC-II
4. SHRI ANIL .D. KALE. CHAIRMAN SEAC-III
5. SECRETARY MOEF & CC
6. IA- DIVISION MOEF & CC
7. MEMBER SECRETARY MAHARASHTRA POLLUTION CONTROL BOARD MUMBAI
8. REGIONAL OFFICE MOEF & CC NAGPUR
9. MUNICIPAL COMMISSIONER MUMBAI
10. MUNICIPAL COMMISSIONER NAVI MUMBAI
11. REGIONAL OFFICE MPCB MUMBAI
12. REGIONAL OFFICE MPCB NAVI MUMBAI
13. REGIONAL OFFICE MIDC ANDHERI
14. REGIONAL OFFICE MIDC KOPER KHAIRANE NAVI MUMBAI
15. MAHARASHTRA STATE ELECTRICITY DISTRIBUTION CO. LTD
16. COLLECTOR OFFICE MUMBAI
17. COLLECTOR OFFICE MUMBAI SUB-URBAN

